


Notes:

- Weir constructed of Reinforced Concrete G25/20
- Weir to be bedded on firm rock throughout.
- Key to be cut into foundation material as shown
- Pipe positioned as shown with gravel filter. Scrap iron lugs should be welded on to fix pipe in wall.
- Weir Height not to Exceed 5.0m
- Weir Length not to Exceed 50m without buttressing
- Suitable downstream slope protection to be placed after construction
- Take additional advice for weirs over 3.0m tall or 30m long
- Keep Crest Width Constant based on Max Height


3" GI with 4 times  $\frac{3}{8}$ " dia holes  
Every 5cm. (offset each row 45 deg)  
Include End Cap (pr similar arrangement)

NOTES

REV	REVISIONS	SIGN	DATE	APPROVED
	BY			
	CHECKED			
	BY			
	CHECKED			
	BY			
	CHECKED			
CO	BY			
	CHECKED			

Client  

**TANA WATER WORKS DEVELOPMENT AGENCY**  
 P.O BOX 1292-10100  
 NYERI

Project  
**PROPOSED KANITHA SMALL DAM**

Civil/Structural Engineers  

**TANA WATER WORKS DEVELOPMENT AGENCY**  
 P.O BOX 1292-10100  
 NYERI

Drawing Title  
**EMBANKMENT WALL DETAILS  
 CROSS-SECTIONAL VIEW**

Designed by BNW	Drawn by BNW
Checked by JMM	Approved by
Scale AS SHOWN (A1)	Date MAR, 2024
Job No. 1	ACAD File:
C STATUS	DRAWING No.TWVWD/KD/EW-01
	CO REV